

56 Prospect Street Hartford, CT 06103

David J. Burnham Eversource ISO Policy and Economic Analysis phone: 860-728-4506

email: david.burnham@eversource.com

October 05, 2021

Ms. Emily Laine Chair, NEPOOL Reliability Committee ISO New England, Inc. One Sullivan Road Holyoke, MA 01040-2841

Dear Ms. Laine,

In accordance with Schedule 12C of the ISO New England ("ISO-NE") Transmission, Markets & Services Tariff ("ISO-NE Tariff"), Eversource Energy Service Company ("Eversource") hereby submits the attached Transmission Cost Allocation ("TCA") application(s) reporting cost support information associated with the construction, retirement, or modification to facilities rated 69 kV and above that qualify as regional Pool Transmission Facilities ("PTF") for the following Eversource project:

ES-21-TCA-53 K105 115-kV Line Laminate Wood Structure and OPGW Replacements Project (North Merrimack substation – Greggs substation)

Eversource is requesting that ISO-NE submit this TCA to the NEPOOL Reliability Committee for review, in accordance with ISO-NE Planning Procedure No. 4 ("PP-4").

If you have any questions, I can be reached via the information listed above.

Sincerely,

David J. Burnham

David J. Burnham

cc: M. Drzewianowski

		TCA	Attachn A Applica	nent <u>B</u> ation For	m					
Applicant: Contact Name:		David J. Burnham		Application	on #:		ES-21-T	CA-53	Date:	Oct-21
Company Name:		Eversource Energy Service Company								
Address 1:		56 Prospect Street								
Address 2:					P Project					
City, State, Zip		Hartford, CT 06103	A	sset Condi				289	<u>-</u>	
Contact Phone #		860-728-4506		•	t related	to CIP-14	77			
Email Address		david.burnham@eversource.com		Yes	Ш	No	X			
2. Project Description:									In Service Date:	<u>May-22</u>
	a.	High Level Project Details:								
		Project Name (If no formal name, then Substation Upgrade, Line	e Upgrade,	etc. are acce	eptable):			ement Proje	Laminate Wood Structure ar ct (North Merrimack substat	
		Project Location (State only): Sta	te:		NH		Cou	inty:	Hillsborough	
	b.	Summary of PTF-related work for Project:	L					· <u>L</u>		
		rrimack substation - Greggs substation) to mitigate deficience all project cost details will be known following closeout of all Summary of Non-PTF-related work for Project:		·		mage, rot, cra	icks and det	eriorateu s	teer mechanical connection	3.
4. Has a transmission Prop	posed	I Plan Application required for this work? Plan Application been approved? rence Proposed Plan Application # and approval date.		Yes Yes (Please che	ck only on	No No	X	J/A X	PPA Number: n/a Approval Date:	
Need For Project:										
5. Need Based On (Check	all C	ategories that apply):								
8	a.	Reliability			X					
ł	b.	Economic								
	c.	Service to new load								
	d.	New generator interconnection								
		Generator Proposed Plan Application Number Generator Proposed Plan Application Date	5							

Page 1
ISO-NE Public

	(Attach copy of cover letter & Generator Proposed Plan Application)
e.	Public Policy Transmission Upgrade (PPTU)
f.	Market Efficiency Transmission Upgrade (METU)
g.	Asset Condition X
h.	Other (specify in line 6)
	iption of the need for this Project. entation relative to the need for this Project.)
	tures remediates the potential for structure failures due to asset condition vulnerabilities. To ensure the continued operability of this line segment, the identified section need to be replaced. Replacing the existing Shield Wire with OPGW improves communication bandwidth, security and continuity in network reliability.

Cost of Project:		
7. Total Project Cost (\$\(\frac{\mathbf{M}}{M}\)) equals PTF + Non-PTF + all other Project Costs:	\$16.503	
8. Total Proposed PTF Costs		
a. Total Proposed PTF Cost of this Project (\$M):	\$16.503	
b. Requested Pool-Supported PTF Costs associated with this Project (\$M):	\$16.503	
c. Breakdown of Requested Pool-Supported PTF Cost associated with this Project (\$M): (Consistent with Table 1 and Appendix D of this Procedure)		
Material	\$1.475	
Labor	\$11.342	
ROW	\$0.000	
Engineering/Permitting/Indirects	\$2.552	
Escalation	\$0.000	
AFUDC (or equivalent)	\$0.542	
Contingency	\$0.592	<u></u>
d. Generator Supported PTF Costs* (\$M):	\$0.000	
If the costs in 8.b. plus 8.d. do not equal the total proposed PTF cost (8.a) explain and indicate who is responsible for the remaining costs.		
9. Total Proposed Non-PTF Cost of this Project (\$M):	\$0.000	
 Proposed PTF Costs (\$M) introduced as a result of local, state or other regulatory/legislative requirements, including costs identified pursuant to Section 1.6.3 of this PP-4. 	\$0.000	
a. Description of Proposed PTF Cost introduced as a result of local, state or other regulatory/legislative requirements as defined in question 8 above.		
11. All other Project Costs not captured in PTF Costs (8) or Non-PTF Costs (9) (\$M) associated with this Project:	\$0.000	
12. Total PTF Cost based on: (check one) Actual Costs OR Estimated Costs* X		
13. Valuation Year(s) of dollar amounts submitted above:		
14. If applicable, explain how the cost of common facilities were allocated between PTF and Non-PTF.		
5. Does this Project result in a change of existing Non-PTF facilities to PTF?	Yes	No X

16. Describe the major transmission alternatives, and their costs consistent with the breakdown provided in item 7 of this Application, that were considered. Provided an explanation why the preferred alternative was selected.	
(Include available documentation relative to the major transmission alternatives analysis and selection.)	
Alternative: Do nothing but for the reasons stated in 6 above is not acceptable.	
<u>Preferred:</u> Field Inspections have indicated a significant amount of degradation and decreased load carrying capacity of laminate wood 115-kV structures (many of the poles should be decay, woodpecker damage, rot and deterioration). Replacing the structures resolves multiple structural/hardware issues and supports safe and reliable operation of the trailine. The installation of the OPGW will provide high speed communications between the substations, reduce dependency on less reliable TELCO services and improve the reliable Transmission system.	nsmission
17. Has state and local siting been completed? If yes, explain the siting process and any provisions that were made during siting, provide docket or siting reference	
numbers. If no, then explain when siting is expected to be completed and any provisions that have been agreed to.	
No unusual siting or permitting was required for this project.	

^{*} Pool-Supported PTF costs were determined pursuant to Schedule 11 of Section II of the Tariff.

PROJECT COST ESTIMATE & SCHEDULE SHEET

Transmission Owner: The Connecticut Light and Power Company

RSP Project #: 289

Project Name: K105 115-kV Line Laminate Wood Structure and

OPGW Replacement Project (North Merrimack substation - Greggs substation)

Date: Oct-21


1. Project Scope Summary

The project will replace 64 laminate wood structures (LWS) with steel structures and 10.8 miles of existing shield wire with Optical Ground Wire (OPGW) on the K105 115-kV Line (North Merrimack substation - Greggs substation). The structure are being replaced due to deficiencies such as: woodpecker damage, cracks, rot and splitting as the result of visual and aerial inspections.

2. Project Cost Summary

(\$M)

2.1. Project C	ost S	ummary				
Cost Category	PTF		Non-P	TF	Total	ı
Material	\$	1.475	\$	-	\$	1.475
Labor & Equipment	\$	11.342	\$	-	\$	11.342
Right of Way	\$	-	\$	-	\$	-
Engineering/Permitting /Indirects	\$	2.552	\$	-	\$	2.552
Escalation	\$	-	\$	-	\$	-
AFUDC	\$	0.542	\$	-	\$	0.542
Contingency	\$	0.592	\$	-	\$	0.592
Total Project Cost	\$	16.503	\$	-	\$	16.503



		7	2.2 Detailed Co	st Summary By	Project Element				
	Material	Labor & Equipment	Right of Way	Engineering/ Permitting/ Indirects	Escalation	AFUDC	Contingency	Total	PTF Amount
K105 115-kV Line Laminate Wood Structure and OPGW Replacement Project (North Merrimack substation - Greggs substation)		\$ 11.342	\$ -	\$ 2.552	\$ -	\$ 0.542	\$ 0.592	\$ 16.503	\$ 16.503
Total	\$ 1.475	\$ 11.342	\$ -	\$ 2.552	\$ -	\$ 0.542	\$ 0.592	\$ 16.503	\$ 16.503

3. Project Milestone Schedule

				2	020)		2021				2022					2023			Т		202	24			2025			Т		20	026	
			Qtr1				tr4 C	tr1 C			tr4 C				Qtr4	Qtr1			Qtr	4 Qt	tr1 (Qtr4	Qtr				tr4(Qtr1			3 Qt
Description	Start	Complete				Perr				,				_					,							_	,						
					П		П				П	П			Ш			П	П	П	П	Ш	П		П	П	П	П	П	П	П	П	П
Approval and Permits	06/01/2021	12/30/2021		T	T				•		→									Т						T							
																			T						-	1							
			E	ngin	iee	ring																											
					П		П		П		Т	П			П			П	П	П	П	Ш	П		П	П	П	П	П	П	П	П	П
Engineering and Design	01/01/2021	11/01/2021		T	T		•							Ш					T		T	m	T			T			T	\square			
														П						П	Т			П		Т						П	
			M	ater	ial																												
				П	П	П			Ш	П	т		П	Ш	Ш			П			Т	Ш	П			П		П	П	П	П	П	Т
Material	07/01/2021	11/30/2021			П				+		-										П		П			П			П				
				T	П					TT			П	ПТ					T		T	Ш				T							
			C	ons	tru	ction	1																										
					П		т				П	П			П			П	ТП	П	П	П	П		П	П	П	П	П	П	П	\Box	П
Construction	11/01/2021	05/30/2022		T	1					1	-		>						1	T					1	1	1					1	
																				Т	1		П									П	
			Qtr1	Qtr	2 Q	tr3 Q	tr4 C	tr1 C	tr2 Q	tr3 Q	tr4 C	Qtr1 C	Qtr2 C	Qtr3	Qtr4	Qtr1	Qtr2	Qtr3	Qtr	4 Qt	tr1 (Qtr2	Qtr3	Qtr4	Qtr	Qtr	2 Qt	r3 Q	tr4 (Qtr1	Qtr2	Qtr	3 Qt
					020				2021				202)23		T		202					2025		1			026	

K105 115-kV Laminate Wood Structure and OPGW Replacements Project Correlation Table (North Merrimack substation - Greggs substation)

TCA Item	<u>RSP:</u> Project ID #	<u>Study:</u> Reliability Issues Requiring <u>Action</u>	PPA No.	PAC/RC Meeting: Presentation Reference	TCA Applic PTF <u>Estimate</u>	cation (\$Ms): Non-PTF Estimate	
ES-21-TCA-53	<u>289</u>	n/a	n/a	Replace 64 laminate wood 115-kV structures with light-duty steel pole structures, including hardware, insulators, and guys and replace 10.8 miles of existing shield wire with Optical Ground Wire (OPGW).	Per PAC Presentation	\$ 16.503 \$ 16.503	<i>ф</i>